



Execution of assembly works consisting in the assembly of additional new tank bottom ring sheets and connecting them with assembly welds (external and internal) to the tank bottom cargae, as well as welding of additional reinforced vertical sheet on the whole outer circumference of the tank bottom cargae and connecting it with welds to the tank bottom ring-ring, and delivery of auxiliary materials, including welding consumables.