



- Assembly of technological pipelines DN350 PN25 (working medium petrol) of approx. 380 m and their incorporation into the existing technological system
- Assembly of technological pipelines DN250 PN16 (working medium petrol) of approx. 420 m and their incorporation into the existing technological system
- Assembly of process fittings, including shut-off valves DN350 PN25 and DN250 PN16 with electric drive in Ex version